



NOTES:

1. PIPE SHALL BE 100mm $\phi$  PERFORATED PVC SDR 28 UNLESS OTHERWISE APPROVED.
2. IN EXTREME CASES, "NATIVE BACKFILL" SHALL BE REPLACED WITH CLEAN (LESS THAN 5% PASSING #200 SIEVE) PIT RUN GRAVEL, AS DIRECTED BY THE ENGINEER.
3. PIPE TO BE LAID WITH PERFORATIONS DOWN IN THE 4 O'CLOCK AND 8 O'CLOCK POSITIONS.

UNITS ARE IN MILLIMETERS  
UNLESS OTHERWISE NOTED

**TYPICAL  
PERFORATED DRAIN  
INSTALLATION**

2	City	Drawings revised	02/99
1	Usi	Original drawings created	04/96
No.	By	Revisions	Date

Date: February 12/99	Scale: N.T.S	Dwg. No. F-5
Drawn by: Bob Smith	Cad file: c:\..\drawings\standard\By_F5	